

WELL PLUGGING RECORD

Give All Information Completely  
Take Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County, Sec. 17 Twp. 24S Rge. (E)23 (W)

Location as "NE/CNW/SW" or footage from lines. C NE NE

Lease Owner Rains & Williamson Oil Co.

Lease Name COLBURN Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-14 1963

Application for plugging filed 11-14 1963

Application for plugging approved 11-14 1963

Plugging commenced 11-14 1963

Plugging completed 11-14 1963

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production ----- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas

Producing formation None Depth to top -- Bottom -- Total Depth of Well 4921 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 25 sacks cement at 700'. Filled hole with rotary mud to 250'. Set plug, spotted 25 sacks cement. Filled hole with rotary mud to 40' of base of cellar. Capped with 15 sacks. Plugging completed at 11:25 P.M., November 14, 1963.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1963

11-20-63

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains, Partner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 63

My commission expires November 8, 1966

Sherry Gish  
Notary Public.

ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co.  
and Hull Drilling Co., Inc.  
#1 COLEBURN, C NE NE  
Section 17-24S-23W  
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson Oil  
COMMENCED: 10-31-63  
COMPLETED: 11-14-63

Remarks: Set 8-5/8" at 253'  
w/140 sacks cement

## Formations:

Surface Clay	35'
Rock	60'
Clay and Shale, Shells	254'
Shale	390'
Sand	465'
Shale and Red Beds	660'
Sand	695'
Shale	1002'
Anhydrite	1015'
Shale	1095'
Dakota Sand	1300'
Red Beds and Shale	1595'
Anhydrite	1630'
Shale and Shells	2380'
Shale and Lime	2830'
Lime and Shale	2900'
Shale and Lime	3385'
Lime and Shale	4090'
Lime	4710'
Lime and Shale	4760'
Lime and Chert	4772'
Lime	4830'
Lime and Chert	4880'
Lime	4905'
Lime and Shale	4921'
Rotary Total Depth (D&A)	4921'

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains  
Partner

Subscribed and sworn to before me, a  
Notary Public in and for the State of  
Kansas, County of Sedgwick, this 18th  
day of November, 1963.

*Sherry Gish*  
Sherry Gish Notary Public

My Commission Expires:  
November 8, 1966

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1963

11-20-63

CONSERVATION DIVISION  
Wichita, Kansas