


WELL PLUGGING RECORD

Give All Information Completely
Note Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 29 Twp. 24 Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines. C SE SE
Lease Owner. PICKRELL DRILLING COMPANY
Lease Name. Pivonka Well No. 1
Office Address. 705 4th Natl Bk Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. January 5 19 63
Application for plugging filed. January 5 19 63
Application for plugging approved. January 5 19 63
Plugging commenced. January 5 19 63
Plugging completed. January 5 19 63
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation. Depth to top. Bottom. Total Depth of Well 4840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	302'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 300'. Set plug. Cemented with
30 sacks cement. Heavy mud to 45'. Set plug.
Cemented with 15 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

1-11-63

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. PICKRELL DRILLING COMPANY
Address. 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebits*
C. W. SEBITS
705 4th National Bk Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 63

My commission expires June 21, 1966
Maxine Blackman
Notary Public.

ROTARY DRILLING LOG

15-083-10199-0000

COMPANY: PICKRELL DRILLING COMPANY Rotary Drilling Commenced 12-17-62
 705 4th National Bank Bldg, Wichita, Kansas
 LOCATION: Pivonka No. 1, G SE SE 29-24-23, Hodgeman County, Kansas Rotary Drilling Completed 1-4-63

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (7 joints) 8 5/8" Surface Casing set at 301', cemented with 215 sacks cement. Circulated. Completed 8:00 P.M. December 17, 1962. No oil string ru. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

100	Top soil, sand	<u>C. F. S.</u>
200	Shale & Shells	4725
450	Blue Shale	4735
590	Shale	4740
700	Sand	4765
1505	Red Bed & Shale	4840
1545	Anhydrite	
1680	Shale	
1770	Red Beds - Shale	<u>Slope Tests</u>
2155	Shale & Shells	2500
2325	Shale & Lime	3000
2835	Lime	3500
2930	Lime & Shale	4000
2895	Lime	
3657	Lime & Shale	
3765	Lime, Shale & Sand	<u>S. L. M.</u>
4130	Lime & Shale	3700
4705	Lime	4130
4730	Chert. Conglomerate	4500
4745	Chert	
4752	Chert & Lime	
4765	Mississippian Chert	
4834	Lime	
4840	Mississippian - TD	

1-11-63
 RECEIVED
 STATE CORPORATION COMMISSION

JAN 11 1963

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 8th day of January, 19 63, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Maxine Blackman Notary Public