


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

15-083-20779-0000 Form CP-4

Hodgeman County, Sec. 27 Twp. 24S Rge. (E) 23W (W)
Location as "NE/CNW&SW" or footage from lines C SW NW
Lease Owner Chief Drilling Co., Inc.
Lease Name Beil-Kennedy Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed Dec. 7, 1980 19
Application for plugging filed Dec. 7, 1980 19
Application for plugging approved Dec. 7, 1980 19
Plugging commenced Dec. 8, 1980 19
Plugging completed Dec. 8, 1980 19
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4750' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	321'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged w/60 sx. @ 720', 30 sx. @ 300', 10 sx. @ 40',
5 sx. in rathole.

12-12-80

DEC 12 1980

CONSERVATION DIVISION
WICHITA, KANSAS


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Warrior Drilling, Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. W. Shelton, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Shelton, Jr.
905 Century Plaza, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1980

My commission expires



Marilyn Lahar
Marilyn Lahar Notary Public.

WELL LOG

15-083-20779-0000

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 BEIL-KENNEDY
C SW NW Sec. 27-24S-23W
Hodgeman County, Kansas

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 321' w/200 sx.

COMMENCED: November 28, 1980
COMPLETED: December 8, 1980

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Clay	0	170	2327 Gr.
Clay & Sand	170	1111	2329 D.F.
Sand & Shale	1111	1464	2332 K.B.
Anhydrite	1464	1500	
Sand & Shale	1500	2081	
Shale	2081	2855	
Lime & Shale	2855	3277	
Shale & Lime	3277	3565	
Lime & Shale	3565	3825	
Shale & Lime	3825	4139	
Lime & Shale	4139	4285	
Lime	4285	4750	
RTD	4750		

D & A

12-12-80
RECEIVED
DEC 12 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the
Driller's Log of the well drilled in the C SW NW Sec. 27-24S-23W,
Hodgeman County, Kansas, to the best
of my knowledge and belief.

CHIEF DRILLING CO., INC.

F. W. Shelton, Jr.

F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 11th day of December, 1980.

MARILYN LAHAR
NOTARY PUBLIC
STATE OF KANSAS
NOT. ACCT. EXP. 4-30-83

Marilyn Lahar
Marilyn Lahar Notary Public