


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

HODGEMAN County, Sec. 17 Twp. 24S Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner SUN OIL COMPANY  
Lease Name Mellecker Well No. 2  
Office Address 1720 S. Bellaire, Denver, CO 80222  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 3 1963  
Application for plugging filed 1-28 1975  
Application for plugging approved 1-30 1975  
Plugging commenced 2-1 1975  
Plugging completed 2-15 1975  
Reason for abandonment of well or producing formation State Regulations  
Require Plugging  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas  
Producing formation Mississippian Depth to top 4720 Bottom 4750 Total Depth of Well 4789 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PULLED IN	PULLED OUT
		0	242	8 5/8	242	0
		0	4788	5 1/2	4788	348

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 50' of sand across perforations. Plug back total depth is 4700'  
Dumped 4 sacks of cement. Shot pipe at 348'. Pulled 10 joints of 5 1/2"  
casing. Displaced hole with 50 sacks of cement, 10 sacks of gel, 35 sacks of  
cement to surface. Well P&A.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1975

CONSERVATION DIVISION  
Wichita, Kansas

2-21-1975

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Charles Crowe Drilling Co.  
Address P. O. Box 706 Hays, Kansas 67601

STATE OF Colorado, COUNTY OF Denver, ss.  
D. A. Coppedge (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. A. Coppedge*

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1975

(Address)

*Mary Marion*

Notary Public.

My commission expires Nov. 22, 1975


DRILLERS' LOG

Company:	Jones-Gebert Oil Co.
Contractor:	Jones-Gebert Oil, Inc.
Farm:	#2 Mellecker, C SE SE Sec. 17-24S-22W Hodgeman County, Kansas
Commenced:	4/20/63
Completed:	5/6/63
Casing:	8 5/8" @ 242 w/200 sx. 5 1/2" @ 4788 w/125 sx.

0 - 242	Red Bed & Shale
242 - 1340	Clay & Red Bed
1340 - 1510	Shale
1510 - 1585	Anhydrite
1585 - 1650	Shale
1650 - 1970	Shale & Shells
1970 - 2350	Shale w/Lime Streaks
2350 - 2530	Lime & Shale
2530 - 2640	Lime & Some Chert
2640 - 2725	Lime
2725 - 2795	Lime
2795 - 2865	Lime
2865 - 2955	Lime
2955 - 3070	Lime w/Shale
3070 - 3155	Brown Lime & Some Chalk
3155 - 3310	Shale w/Lime Streaks
3310 - 3460	Shale w/Lime & Chalk Streaks
3460 - 3536	Shale w/Lime & Chalk Streaks
3536 - 3650	Shale w/Lime & Chalk Streaks
3650 - 3755	Lime & Shale
3755 - 3860	Lime & Shale
3860 - 3970	Shale w/Lime & Chalk Sections
3970 - 4024	Shale & Lime
4024 - 4118	Shale & Lime w/Chalk Streaks
4118 - 4173	Lime & Shale - K.C. (?)
4173 - 4215	Lime
4215 - 4272	Lime
4272 - 4346	Lime w/Chert & Chalk
4346 - 4394	K.C. Lime
4394 - 4432	Lime
4432 - 4477	Lime
4477 - 4531	Lime & Shale
4531 - 4578	Lime & Shale
4578 - 4598	Lime & Shale
4598 - 4630	Lime & Shale
4630 - 4678	Lime & Shale
4678 - 4710	Lime & Shale
4710 - 4715	Mississippian
4715 - 4725	Mississippian
4725 - 4740	Mississippian
4740 - 4785	Mississippian
4785	T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1975  
CONSERVATION DIVISION  
Wichita, Kansas

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #2 Mellecker, C SE SE<sub>2</sub>, Sec. 17-24S-22W, Hodgeman County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.



George R. Jones

State of Kansas - County of Sedgwick ) ss.  
Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 9th day of May, 1963.



Barbara J. Layton

My Commission Expires:  
February 1, 1964

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1975  
CONSERVATION DIVISION  
Wichita, Kansas