

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

November 16, 1972

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1972 11-22-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford, Jr. of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Acme Oil Corporation

Complete Address: 6235 W. Kellogg, Wichita, Kansas

Lease Name: Callias Well No. 1

Location: SE SE NE Sec. 26 Twp. 25 Rge. 4 ~~(E)~~ (W) X

County: Reno Total Depth 4081' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Crawford was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/2 sack hulls to 240' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent