



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-30-64
NOV 30 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Townsend of Livingston Oil Co. has this

date requested permission to plug the following described well:

Mr. Townsend guarantees payment of the plugging fee.

Operator's full Name: Livingston Oil Co.

Complete Address: Box 1797 Tulsa, Okla.

Lease Name: Murphy Unit # 1 Well No. 0-5-40

Location: NE/4 SW/4 Sec. 5 Twp. 24S Rge. 40 (E/W)

County Hamilton Total Depth 2425' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Townsend was instructed to plug the well as follows:

8 5/8"-126' Circulated w/cement. 4 1/2"-2425' Cemented.

Top perforations-2357' Plug back to 2412'

Plug bottom w/20 Sax.cement top cement 2200' Mud 2200' to 150'

50 Sax.cement 150' to 0.

Very truly yours,

Conservation Division Agent