

State of Kansas



15-075-10115-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

11-4-66  
RECORDED  
STATE CORPORATION COMMISSION  
NOV 4 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Building, Wichita, Kansas

Lease Name: H.W. Gregory Well No. 1

Location: App. Center Sec. 27 Twp. 24 Rge. 41 (E) (W)

County Hamilton Total Depth 2390' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

7" to 260' circulated w/ cement. 4 1/2" to 2390' ciru. w/ cement.

Plug bottom w/ 10 sacks cement. Top of cement 2100'

Mud 2100' to 300' Spotted 10 sacks cement 300' to 200'

Mud 200' to 60' Plug, Halls & 5 sacks cement 60' to 0'.

Very truly yours,

Edgar J. Lives  
Conservation Division Agent