



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1964
 2-17-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Duncan of R.W. Lange has this date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: R.W. Lange

Complete Address: Box 1034 Garden City, Kansas

Lease Name: Pollyanna Well No. 1

Location: SE SE Sec. 36 Twp. 27S Rge. (E) (W) 35

County Grant Total Depth 5659 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Duncan was instructed to plug the well as follows:

8 5/8"-670' Circulated w/cement. 5 1/2"-4650' Cemented.

Plug back w/baker bridge plug at 3050' DV Tool at 2900'

Perforations 3035' to 2929' Plug bottom w/20 Sax.cement 3050'-2829'

Mud 2829' to 650' Spotted 10 Sax.cement 650' to 550'

Mud 550' to 50' Plug 25 Sax.cement 50' to 0

Very truly yours,

Conservation Division Agent