



15-047-21003-0000

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

26 January 1982

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 2 1982

CONSERVATION DIVISION  
Wichita, Kansas

2-2-82

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-047-21003

Dear Sir:

Mr. Doyle Tolberts of D. R. Lauck Lauck Drilling Co has this

date requested permission to plug the following described well:

Operator's Full Name: D. R. Lauck Oil Co. Inc.

Complete Address: 221 South Broadway Suite 400 Wichita Kansas 67202

Lease Name: Farber Well No. C 1

Location: 25' East N/C SW NW Sec. 30 Twp. 25S Rge. 16W (E) (W)

County: Edwards Total Depth: 4565'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Tolberts was instructed to plug the well as follows:

There is 145' of 10 3/4" conductor pipe + 383' of 8 1/2" surface casing  
cement circulated. The Anhydrite was topped at 1063'. 1st plug  
at 900' with 40 Sbk of cement. 2nd plug pushed rubber  
plug to 360' and pumped 35 Sbk of cement on top of it. 3rd  
plug at 40' to 0' on solid bridge with 10 Sbk of cement. They  
also pumped 10 Sbk of cement in rat hole + 3 Sbk of cement in  
mouse hole. Plugging accomplished by Allied Cementing  
water well.

Very truly yours,

Raul Luthie

Conservation Division Agent