

15-047-10142-0000

FORM - CP-2
Rev. 6-26-62

State of Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1966
8-29-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name: Wilson Well No. # 1

Location: NW NW SE Sec. 34 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4525 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Watson was instructed to plug the well as follows:

380' of 8 5/8" surface pipe, cemented with 225 sacks.

4525' of 5 1/2" long string, cemented with 100 sacks.

Plugged back to 4380'. Top perforation 4358'. Sand to

4340', cement with 5 sacks. Fill hole with mud to 300',

10', rock bridge, cement with 20 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Archie Elving
Conservation Division Agent