

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION

SEP 12 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crandall of Vernon Faulconer has this
date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Vernon Faulconer

Complete Address: 336 Union Center, Wichita, Kansas

Lease Name: Ediger Well No. 1

Location: C S/2 SW Sec. 34 Twp. 32 Rge. 29 (W)

County Meade Total Depth 5800' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crandall was instructed to plug the well as follows:

9" to 1426' circulated w/ cement. 5 1/2" to 5798' cemented.

No perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 5675' Mud 5675' to 700'

Rock bridge & 40 sacks cement 700' to 575' Mud 575' to 35'

Plug, Halls & 10 sacks cement 35' to 0'

Very truly yours,

Edward A. Evers
Conservation Division Agent