



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Hoberecht of Skelly Oil Co. has this date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co.

Complete Address: Box 649 Mc/Cook, Nebraska

Lease Name: Ann Keehn Well No. # 1

Location: C NW SW Sec. 22 Twp. 32 Rge. (E) (W) 30

County Meade Total Depth 5685 Oil Well x

Gas Well      Input Well      SWD Well      D & A x Lost Hole     

Mr. Hoberecht was instructed to plug the well as follows:

8 5/8"-1428' Circulated w/cement. 5 1/8"-5684' Cemented.

Plug back to 5567' w/cement. Top Perforations 5551'

Plug bottom w/sand to 5540' 20 Saz. cement 5540' to 5380'

Mud 5380' to 700' Spotted 35 Saz. cement 700' to 600'

Mud 600' to 45' Plug, 15 Saz. cement 45' to 0

Very truly yours,

*J. P. Roberts*  
 Conservation Division Agent