



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

### VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

OCT 16 1962

RECEIVED CONSERVATION DIVISION  
 STATE CORPORATION COMMISSION  
 Wichita, Kansas

OCT 16 1962  
 CONSERVATION DIVISION  
 STATE CORPORATION COMMISSION  
 WICHITA, KANSAS

10-16-1962

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date Oct. 8, 1962, 1962, authorized  
 the following plugging operation:

Operator's full Name: Pure Oil Co.

Complete Address: Box 9545 Oklahoma, City Oklahoma.

Lease Name: M. C. McGuire Well No. #1

Location: SW <sup>NW</sup> SE Sec. 20 Twp. 39 Rge. 10 (E) (W) X

County Barber Total Depth 4444'

Oil Well      Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: Abandoned Oil Well

Operator was instructed to plug well as follows:

4444' of 4 1/2" pipe. Sanded to 4420' and 3 sacks cement.

Perforation between 4425' and 4430'. 269' of 8 5/8'

surface pipe circulated with 250 sacks cement. Hole filled

to 180' with mud, 10' rock bridge, 20 sacks cement. Hole filled

to 35' with heavy mud, 10' rock bridge and 10 sacks cement  
to base of cellar.

Very truly yours,

*Herbert J. ...*  
 Conservation Division Agent