

State of Kansas



15-079-20049-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Miller of Kern Drilling Co. Inc. has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Kern Drilling Co. Inc.

Complete Address: Box 699 Magnolia, Arkansas. 71753

Lease Name: Redinger Well No. # 1

Location: SE NE SW Sec. 7 Twp. 24 Rge. 2 (E) (W)

County Harvey Total Depth 3925' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Miller was instructed to plug the well as follows:

8 5/8"-482'-Circulated w/cement.

Mud 3925' to 1420'. 50 Sax. cement spotted at 1420' thru drill pipe.

Mud top cement to 450'. Plug, Hulls, 25 Sax. cement 450' to 375'.

Mud 375' to 40'. Plug, Hulls, 10 Sax. cement 40' to 0.

5 Sax. cement in rat hole. Gas showing at 1400'.

Globe Cementing Company.

Very truly yours,

*Hugh Scott*  
Conservation Division Agent