

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 2/26/52 (of this well). 1/89
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Ensign Operating Co. OPERATOR'S LICENSE NO. 04782

ADDRESS 621 17th Street, Ste 1800
Denver, Colorado 80293 PHONE # (303) 293-9999

LEASE (FARM) Burnside WELL NO. 'A' 1 WELL LOCATION 150'S. and W. of Center COUNTY Fl

SEC. 29 TWP. 24 RGE. 32 or (W) TOTAL DEPTH 2676 PLUG BACK TD 2582
2490' FSL 2790' FEL

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 10 3/4" SET AT 323' CEMENTED WITH 175 SACKS

CASING SIZE 7" SET AT 2558' CEMENTED WITH 800 SACKS

PERFORATED AT Open Hole from 2558' to 2582'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING See attachments.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1989

5-15-89

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Reed Wacker PHONE # (316) 276-3267

ADDRESS Ensign Operating Co., P.O. Box 937, Garden City, Ks. 67846

PLUGGING CONTRACTOR Post and Mastin Well Service LICENSE NO. 0843B 6/89

ADDRESS P.O. Box 297, Garden City, Ks. 67846 PHONE # (316) 276-3442

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Reed Wacker
(Operator or Agent)

DATE: 5/12/89

①

PLUG TO ABANDON PROCEDURE

Burnside #A-1
150' S & W of Center
Section 29-T24S-R32W
Finney County, Kansas

1. Move in and rig up completion tools. Pick up 2-3/8" tubing (work string) and run in hole to 2400', at top of CIBP.
2. Plug to abandon as follows:
 - a. Circulate hole with 100 bbls of water containing 15 sx of bentonite gell and 2 sx of cotton seed hulls;
 - b. Circulate 50 sx of cement to spot from 2400' back to 1900'. Cement 60/40 Pozmix, 2% gell;
 - c. Circulate 50 sx of cement to spot from 1450' back to 950';
 - d. Circulate 35 sx of cement to spot from 335' back to 3'; and
 - e. Cut off and cap surface casing and production casing 3' below ground level.
3. Rig down completion tools

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1989
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

Kansas Corporation Commission

THIS NOTICE

AUG 16 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

May 16, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

Ensign Operating Company
621 17th Street, Ste. 1800
Denver, CO 80293

Burnside "A" #1
2490'FSL 2790'FEL
Sec. 29-24S-32W
Finney County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760