

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petrop International Oil Co.

Complete Address: 700 Petroleum Bldg., Tulsa, Oklahoma

Lease Name Lamb Well No. # 1

Location C NW SE Sec. 30 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4380

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 6:00PM Day 6th Month July Year 1963

The Above well was plugged as follows:

400' of 8 5/8" surface pipe, cement circulated with 250 sacks. 4378'
of 4 1/2" long string, cemented with 100 sacks. Top perferation 4314'.
Sanded to 4300', cemented with 3 sacks. Hole was bailed down to 240',
plug was set at 240', 10' rock bridge, cemented with 20 sacks. Hole
was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar.
3115' of 4 1/2" long string recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-16-63

INV. NO. ~~7444~~ W 7390-W