

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 28 1966  
CONS. DIVISION  
WICHITA, KAN.

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Lamb Well No. # 1

Location SW SW SW Sec. 30 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4400'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 12:45 PM Day 25th Month June Year 1966

The Above well was plugged as follows:

400' of 8 5/8" surface pipe, cement circulated. 4390' of 4 1/2" long string,  
cemented with 100 sacks. Plug back T.D. 4359'. Top perforation 4274'.

Bottom of the hole was sanded to 4250', and cemented with 5 sacks, through  
the dump bailer. 3871' of 4 1/2" long string was recovered from the hole.

Bridge plug was pushed in fluid to 225', rock bridge from 225' to 215'.

7 sacks of cement was mixed in a barrel, and put on plug at 215', through  
the dump bailer, and let set over-night. Next day hole was bailed dry, and  
18 sacks of cement was added to the plug. Hole was filled with mud to 40',  
rock bridge from 40' to 30', and cemented with 10 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/28/66

INV. NO. 3473-W

Signed: Archie Elving  
Well Plugging Supervisor