

15-185-01578-0000

Form CP-3
Rev. 6-26-62

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1966
6-28-65

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Lamb Well No. # 2

Location C SE SW Sec. 30 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4372'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 5:30PM Day 27th Month June Year 1966

The Above well was plugged as follows:

411' of 8 5/8" surface pipe, cemented with 350 sacks. 4370' of 5 1/2" long string
cemented with 150 sacks. Top perforation 4278'. Bottom plug and 25' of sand
to 4260', and cemented with 5 sacks, through the dump bailer. 3274' of 5 1/2"
long string was recovered from the hole. Bridge plug was pushed in fluid to
325', rock bridge from 325' to 315'. 5 sacks of cement was mixed in a barrel,
and put on plug at 315', through the dump bailer, and let set over week-end,
Hole was bailed dry and 20 sacks of cement was added to the plug. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sack
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/28/66

INV. NO. 3492-W