

15-047-10098-0001

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name F.G. Holl

Complete Address 6724 E. Kellog, Wichita, Ks. 67207

Lease Name Martin-Spain Well No. 1

Location NW NE Sec. 1 Twp. 25S Rge. 16 (E)  (W)

County Edwards Total Depth 4220

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1:15 Pm. Day 7 Month 12 Year 1979

The above well was plugged as follows:

245' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 4219' w/150  
sax cement. Plug back to 4050'-Preforated at 3920'-Sun mixed & pumped  
35 sax comm. cement from 4020' back to 3571'-Pull 2280' 4 1/2" casing  
Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement  
w/4% gel & 3% cc to top of casing. Shut in w/0 pressure. ED

STATE CORPORATION COMMISSION

DEC 10 1979

12-10-79

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed:   
Well Plugging Supervisor

DATE 12-11-79

INV. NO. 1066-w