

15-047-30078-0000

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1966
10-7-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 South Broadway, Wichita, Kansas

Lease Name Wilson Well No. # 1

Location C SW Sec. 2 Twp. 25 Rge. 16 (E) (W)

County Edwards Total Depth 4356'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Lauck Drilling Company, Inc.

Address: 301 South Broadway, Wichita, Kansas License No.

Operation Completed: Hour 8:45PM Day 5th Month Oct. Year 1966

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cement circulated with 235 sacks. Fluid
level in the hole was at 111'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 300', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/7/66
INV. NO. 4064-u