

Form CP-3
Rev. 6-26-62

2
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assttnt Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 17, 1968.

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Joe Branum

Complete Address: Box 348, Russell, Kansas 67665

Lease Name Breitenbach Well No. # 1

Location SW SW SW Sec. 5 Twp. 25 Rge. 16 (E) (W)W

County	Edwards	Total Depth	4574'
--------	---------	-------------	-------

[illegible]

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 3:30PM Day 22nd Month January Year 1968

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated. 4498' of 5 1/2" long string,
cemented with 150 sacks. Plug back T.D. 4470'. Top perforation 4384'. Bottom
of the hole was sanded to 4350', and cemented with 5 sacks. 2431' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 225',
bridge plug and rock bridge from 225' to 215'. 1 sack of Cal-Seal and 1/2 sack
cement was mixed in a barrel, and put on plug at 215', through the dump bailer,
and let set for 1 1/2 hours. Hole was bailed dry, and 25 sacks of cement was add-
ed to the plug, with cement from 215' to 135'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30'
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/23/68
INV. NO. 9732-4

Signed: Arlie Elving
Well Plugging Supervisor