

94  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 18 1963  
12-18-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name Ploog Well No. 4

Location SW $\frac{1}{4}$  Sec. 33 Twp. 18 Rge. 9 (E) (W)X

County Rice Total Depth 3210'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5:30 PM Day 16 Month December Year 1963

The Above well was plugged as follows:

Hole filled with sand to 3190' and cemented with 6 sacks.

Hole filled with mud to 210'. Rock bridge set from 210' to 200' and

hole cemented with 40 sacks. Hole filled with mud to 35'. Rock bridge

set from 35' to 25' and hole cemented to base of cellar with 20 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arthur J. Lerner  
Well Plugging Supervisor

DATE 12/18/63

INV. NO. 8306-W