



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

15 February 1982

RECEIVED  
STATE CORPORATION COMMISSION

FEB 17 1982

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-097-20858-000

Dear Sir:

Mr. Herb Boyberger of Dunne & Gardner Petroleum Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: Dunne-Gardner Petroleum Inc.

Complete Address: 200 West Douglas Suite 250 Wichita Kan 67202

Lease Name: Thompson Well No. 1

Location: C-SE-NE Sec. 21 Twp. 27 Rge. 17W (E) (W)

County: Kiowa Total Depth: 4825'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Boyberger was instructed to plug the well as follows:

They set 313' of 8 5/8 cement circulated with 225 bbl of cement.  
The anhydrite was topped at 1061'. 1st plug at 1050' with 50 bbl  
2nd plug pushed rubber plug to 300' and pumped 35 bbl on top of it. 3rd  
plug 40' to 0' with 10 bbl of cement on solid bridge. Then circulate 10 bbl  
of cement in rat hole and pumped 3 bbl cement in water well. The  
cement was pumped through drill pipe. The plugging was  
accomplished by sun cementing.

Very truly yours,

Paul Luthi  
Conservation Division Agent