



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-093-20108-0000

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of D&F has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Davies & Fitzgerald

Complete Address: 1303 Philtower Bldg., Tulsa, Oklahoma

Lease Name: U.S.A. Well No. 1-12

Location: 1980' FWL & 1980' FSL Sec. 12 Twp. 26 Rge. 35 (E) (W)

County: Kearny Total Depth 5210' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

8 5/8" to 747' circulated w/ cement. Mud 5210' to 2800'

Spot 150 sacks cement 2800' to 2350' Mud 2350' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent