

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 31 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Burke Well No. 1

Location: C SW SW Sec. 16 Twp. 24 Rge. 21 (E)(W)

County Hodgeman Total Depth 4897' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

8 5/8" to 329' circulated w/ cement. T.D. 4897'

Mud 4897' to 700' Spot 30 sacks cement 700' to 600'

Mud 600' to 380' Spot 35 sacks cement 380 to 280'

Mud 280' to 45' Plug, Halls & 15 sacks cement 45' to 0

Pump

Very truly yours,

*Edgar J. Lewis*  
Conservation Division Agent