



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Brody of Thunderbird has this

date requested permission to plug the following described well:

Mr. Brody guarantees payment of the plugging fee.

Operator's full Name: Thunderbird & Petroleum Resources

Complete Address: Box 18407, Wichita, Kansas

Lease Name: Burke "A" Well No. 1

Location: SW SE Sec. 16 Twp. 24 Rge. 21 (E)(W)

County: Hodgeman Total Depth 4810' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Brody was instructed to plug the well as follows:


8 5/8" to 327' circulated w/ cement. Mud 4810' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 325'

Spot 30 sacks cement 325' to 225' Mud 225' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent