



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Burke "A" Well No. 1

Location: C NE NW Sec. 16 Twp. 24 Rge. 21 XX (E) (W)

County: Hodgeman Total Depth 4703' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Burton was instructed to plug the well as follows:

8 5/8" to 225' circulated w/ cement. Mud 4703' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 225'

Spot 30 sacks cement 225' to 125' Mud 125' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent