



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 14 1964
 1-14-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morgan of James W. Hershberger has this date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: Wichita, Kansas

Lease Name: Burmeister Well No. 1

Location: SW NW Sec. 15 Twp. 24 Rge. (E) (W) 21

County Hodgeman Total Depth 4844' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

8 5/8"-296' Circulated w/cement.

Mud 4844' to 700' 25 Sax. cement spotted 700' to 625'

Mud 625' to 290' 25 Sax. cement spotted 290' to 215'

Mud 215' to 40' Plug, Halls, 15 Sax. cement, 40' to 0

Very truly yours,

[Signature]
 Conservation Division Agent