



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Roy Deck of Wilcox Oil Company has this

date requested permission to plug the following described well:

Mr. Roy Deck guarantees payment of the plugging fee.

Operator's full Name: Wilcox Oil Company

Complete Address: Box 1440 Tulsa, Okla.

Lease Name: Nall Well No. # 1

Location: C SW SE Sec. 1 Twp. 24S Rge. (E) (W) 23

County Hodgeman Total Depth 4748' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Roy Deck was instructed to plug the well as follows:

8 5/8" 278' Circulated w/cement. 4 1/2" 4748' Cemented.

Top of perforations 4594' to 4748'

Plug bottom w/sand 4748' to 4580' 5 sax.cement 4580' to 4520'

Mud 4520' 275' Plug and 35 sax.cement 275' to 175'

Mud 175' to 50' 10' Rock Bridge 50' to 40'

15 sax.cement 40' to Surface.

Very truly yours,

*Alugh Scott*  
Conservation Division Agent