



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 12 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Blevins of James W. Hershberger has this date requested permission to plug the following described well:

Mr. Blevins guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: Wichita, Kansas

Lease Name: Schuette Well No. 1

Location: SE/4 NW/4 Sec. 14 Twp. 24 Rge. 21 (E) (W)

County Hodgeman Total Depth 4815' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevins was instructed to plug the well as follows:

8 5/8" - 265' Circulated w/cement.

Mud 4815' to 600' Spotted 25 Sax.cement 600' to 525'

Mud 525' to 250' Plug.Hulls,25 Sax.cement 250' to 175'

Mud 175' to 40' Plug.Hulls,15 Sax.cement 40' to surface.

Very truly yours,

[Signature]
 Conservation Division Agent