



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 6 1964

1-6-64

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Walker of Rains-Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains-Williamson Oil Co.

Complete Address: 1425 Wichita Plaza. Wichita, Kansas

Lease Name: Schaffer Well No. 1

Location: C SE SW Sec. 3 Twp. 24 Rge. (E) (W) 23

County Hodgeman Total Depth 4845' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Walker was instructed to plug the well as follows:

8 5/8"-249' Circulated w/cement.

Mud 4845' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 250' Spotted 25 Sax.cement 250' to 175'

Mud 175' to 40' Plug,Hulls,15 Sax.cement 40' to 0

Very truly yours,

*[Signature]*  
 Conservation Division Agent