

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-083-30094-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Shipley of Graybol Oil Corporation has this  
date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 N.B.T. Building, Tulsa, Oklahoma

Lease Name: Colburn Well No. 1

Location: C SW NW Sec. 17 Twp. 24 Rge. 23 (N) (W)

County Hodgeman Total Depth 4900' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

8 5/8" to 299' circulated w/ cement. T.D. 4900'

Mud 4900' to 700' Spotted 30 sacks cement 700' to 600'

Mud 600' to 350' Spotted 35 sacks cement 350' to 250'

Mud 250' to 45' Plug, Halls & 15 sacks cement 45' to 0

Very truly yours,

Edward J. Eves  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1966  
7-29-66  
CONSERVATION DIVISION  
Wichita, Kansas