


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hamilton County. Sec. 23 Twp. 24S Rge. (E) 39(W)
Location as "NE/CNW/SW" or footage from lines C/NW SE

Lease Owner Texaco Inc.
Lease Name Foreman Trust Unit Well No. 1
Office Address 614 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 12-16-1961
Application for plugging filed 7-10-1964
Application for plugging approved 7-14-1964
Plugging commenced 7-14-1964
Plugging completed 7-17-1964
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production 7-1-1963
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublett, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Herrington-Krider	Gas	2352	2372	8-5/8	367	None
Winfield	Gas	2402	2415	4-1/2	2549	2026

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 2417-2283 w/10 sx cmt.
2283-600 w/hvy drlg mud
600-525 w/25 sx cmt
525-350 w/hvy drlg mud
350-275 w/25 sx cmt
275-45 w/hvy drlg mud
45-3' below GL w/15 sx cmt

RECEIVED
STATE CORPORATION COMMISSION
8-20-64
AUG 20 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent Casing Pulling Service
Address Liberal, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
H. N. Wade (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
614 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 64

My commission expires 6-20-68 A. E. Boyd Notary Public.


15-075-00076-0000

TEXACO INC. LOG OF WELL

Tulsa

DIVISION

LD # 161983 207796
161995 211043
161988 211345



WELL Foreman Trust Unit LD FILE NO. 162525
LOC Ctr NW SE SEC 23 TWP. 24S RGE. 39W

DIST Wichita CO. PARISH Hamilton STATE Kan-4S

COMM. DRLG 11-19-61 COMP. DRIG. 11-25-61 DAYS DRLG. 6

ROY. FROM 0 TO 2550 CABLE FROM _____ TO _____

CONTR. OR CO. RIG NO. _____ T. D. DRILLED 255

COMP. T. D. 2417 ZERO ELEV. DF 3180.5 GRD. ELEV. 3178 CSG FLC ELEV. 3178

DATE OF FIRST PROD. 12-5-61 OFFICIAL COMP. DATE 12-16-61

LOGS RUN Laterolog, Sonic Log

CASING RECORD

SIZE INCHES	DEPTH FEET	WEIGHT #. FT	GRADE	RANGE	REMARKS--QUAN. CMT. TEMP. SURV. ET.
8-5/8	367	22.7#	SW		Set & cmtd 8-5/8" SW Csg @ 367' w/225 sx Pozmix HA-5.
4-1/2	2549	9.5#	J-55		Set & Cmtd 4-1/2" J-55 Csg @ 2549' w/100 sx Pozmix.

7-14-64

COMPLETION DATA

FORMATION	<u>Herrington, Krider, Winfield</u>		
DATE OF TEST	<u>12-10-61</u>		
DEPTH OF PROD. INTERVAL	<u>2352-56, 2358-66, 2370-72, 2402-15.</u>		
INITIAL PRODUCTION	OIL - BPD		
	GAS MCF	<u>1569</u>	
	WATER - BPD	<u>Slight Spray</u>	
	GOR		
	BHP - PSI		
CORRECTED API GRAVITY			
PRODUCING CONDITIONS	<u>Flowing</u>		
ARTIFICIAL STIMULATION	<u>250 gal. 15% BDA 15x15 gelled acid frac</u>		

REMARKS

Texaco Inc. Interest: 75%

Mobil Oil Co. Interest: 25%

WELL Foreman Trust Unit FIELD Hugoton AREA Liberal

