

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-075-20,283-0000

LEASE NAME Walters

WELL NUMBER 1

C N $\frac{1}{2}$  Ft. from S Section Line  
                     Ft. from E Section Line

SEC. 23 TWP. 24 RGE. 39 (E) or (W)

COUNTY Hamilton

Date Well Completed                     

Plugging Commenced 9-16-87

Plugging Completed 9-18-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Wallace Oil & Gas Inc.

ADDRESS 50 Penn Place Suite 850 Oklahoma City, Okla.

PHONE# (405) 840-2636 OPERATORS LICENSE NO. 5855

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Steve Durant

Is ACO-1 filed?                      If not, is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 2498

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	556	none
				4 1/2	2497	1510

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Pump 20 sks. of cement & 1 sk. of hulls @ 2484 to 2250  
Pump 20 sks. of cement @ 1500 to 1400  
Pump 50 sks. of cement @ 600 to 500  
Put 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Seward, ss. OCT 15 1987

Dan F. Wallace (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

\*(Signature) [Handwritten Signature]  
(Address) 50 Penn Pl., Ste. 850, OKC, OK 73118

SUBSCRIBED AND SWORN TO before me this 12 day of October, 19 87  
10-21-87

My Commission Expires: Jean Guyer Notary Public Jean Guyer  
June 11, 1991



15-075-20283-0000

**Schlumberger**

SIMULTANEOUS  
**COMPENSATED NEUTRON-  
FORMATION DENSITY**

COUNTY **HAMILTON**  
FIELD **KANSAS-HUGOTON**  
LOCATION **23-24S-39W**  
WELL **WALTERS #1**  
COMPANY **WALLACE OIL AND GAS**

COMPANY **WALLACE OIL AND GAS, INC.**  
WELL **WALTERS #1**  
FIELD **KANSAS-HUGOTON**  
COUNTY **HAMILTON** STATE **KANSAS**

LOCATION **2280'FWL & 1250'FNL**  
API SERIAL NO. SEC. TWP. RANGE  
**23 24S 39W**

Other Services:  
**DLL/MSFL/GR**  
*Ra to gen*

Permanent Datum: **GROUND LEVEL**; Elev.: **3246**  
Log Measured From **KB**, **8** Ft. Above Perm. Datum  
Drilling Measured From **KB**

Elev.: K.B. **3254**  
D.F. **----**  
G.L. **3246**

Date	<b>6-19-79</b>					
Run No.	<b>ONE</b>					
Depth-Driller	<b>2485</b>					
Depth-Logger	<b>2475</b>					
Bitm. Log Interval	<b>2474</b>					
Top Log Interval	<b>1800</b>					
Casing-Driller	<b>8 5/8 @ 556</b>		<b>@</b>	<b>@</b>		<b>@</b>
Casing-Logger	<b>556</b>					
Bit Size	<b>7 7/8</b>					
Type Fluid in Hole	<b>STARCH</b>					
Dens.	<b>9.4</b>	<b>48</b>				
pH	<b>7.4</b>	<b>7.6 ml</b>		<b>ml</b>	<b>ml</b>	<b>ml</b>
Source of Sample	<b>MUD PIT</b>					
Rm @ Meas. Temp.	<b>.062 @ 80 °F</b>		<b>@ °F</b>	<b>@ °F</b>		<b>@ °F</b>
Rmf @ Meas. Temp.	<b>.054 @ 70 °F</b>		<b>@ °F</b>	<b>@ °F</b>		<b>@ °F</b>
Rmc @ Meas. Temp.	<b>---- @ -- °F</b>		<b>@ °F</b>	<b>@ °F</b>		<b>@ °F</b>
Source: Rmf	<b>EMT</b>	<b>--</b>				
Rm @ BHT	<b>.050 @ 90 °F</b>		<b>@ °F</b>	<b>@ °F</b>		<b>@ °F</b>
TIME	Circulation Stopped	<b>1230</b>				
	Logger on Bottom	<b>1530</b>				
Max. Rec. Temp.	<b>90 °F</b>		<b>°F</b>	<b>°F</b>		<b>°F</b>
Equip.	Location	<b>7688 LIBERAL</b>				
Recorded By	<b>RUSNAK</b>					
Witnessed By Mr.	<b>WALLACE</b>	<b>JORDAN</b>				