

15-047-00383-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Edwards County, Sec. 27 Twp. 25 Rge. 16 (E) W (W)

Location as "NE/CNW/SE" or footage from lines C SW SE

Lease Owner Specter Pipe & Supply, Inc.

Lease Name ~~XXXXXXXXXX~~ Cudney Well No. 3

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-25-59 1959

Application for plugging filed Sept. 28, 1971 1971

Application for plugging approved Sept. 30, 1971 1971

Plugging commenced 10-20 1971

Plugging completed 10-20 1971

Reason for abandonment of well or producing formation _____

dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

G. R. Biberstein

Name of Conservation Agent who supervised plugging of this well _____

Producing formation Viola Depth to top 4460 Bottom 4482 ft. Total Depth of Well 4483 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	370 ft.	none
				5 1/2" OD	4482 ft.	3732.26

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 4470

Pumped 2 sacks of hulls

Pumped 15 sacks of mud

Pumped 100 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling

Address Rt. 4 Great Bend, Ks 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

[Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1971

Ruth E. Miller

Notary Public.

My commission expires January 5, 1973

15-047-00383-COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. NATIONAL COOPERATIVE REFINERY ASSOC.
Farm. Rex Cudney No. 3

SEC.. 27 T. 25 R. 16W
C SW SE

Total Depth. 4483'
Comm. 3-10-59 Comp. 3-25-59
Shot or Treated.
Contractor. Gabbert-Jones Drig.
Issued. 7-11-59

County Edwards
KANSAS



CASING:

8 5/8" 370' cem w/225 sx.
5 1/2" 4482' cem w/100 sx.

Elevation. 2065' RB

Production. 76 BOPD

Figures indicate Bottom of Formations.

sand	205
shale	370
red bed	1055
Anhydrite	1090
shale & shells	2000
lime	2205
lime & shale	2335
lime	2500
lime & shale	2800
shale & shells	3005
lime & shale	3540
lime	3654
lime & shale	3752
lime	4245
lime & shale	4335
lime	4483
Total Depth	

TOPS: SCOUT

Anhydrite	1055
Heebner	3733
Toronto	3751
Douglas	3772
Brown Lime	3876
Lansing	3891
Cherokee Sand	4343
Conglomerate Chert	4360
Kinderhook Sand	4392
Viola	4460

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1971
CONSERVATION DIVISION
Wichita, Kansas