

15-047-20692-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 27 Twp. 25S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NE

Lease Owner Eagle Petroleum Corporation
Lease Name Cudney Well No. 1
Office Address 104 S. Broadway, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 19, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced June 19, 1980
Plugging completed June 19, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 14,480'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	422'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,480 ft. (rotary total depth) to 420 ft. Set plug at 420 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 420 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 2 sacks cement in water well.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1980 7-3-80

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Employee of owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water - Suite 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Eagle Petroleum Corporation
 FARM Cudney NO. 1

SEC. 27 T.25S R.16W
 LOC. SE NW NE
 COUNTY Edwards

ROTARY TOTAL DEPTH 4,480'
 COMM. June 9, 1980 COMP. June 19, 1980
 CONTRACTOR H-30, Inc. (Rig #2)
 ISSUED July 1, 1980

CASING

10 3/4"
 8 5/8" Set at 422' cemented w/275 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 2,066' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	70'
Sand and Shale	424'
Sand, Shale and Shells	1,015'
Sand and Shale	1,072'
Anhydrite	1,087'
Shale	1,645'
Shale and Lime	2,608'
Lime and Shale	2,855'
Shale	3,115'
Lime and Shale	3,285'
Shale	3,677'
Lime and Shale	3,951'
Shale and Lime	4,040'
Lime	4,480'
Rotary Total Depth	4,480'

I hereby certify the above and foregoing to be
 a true and correct log of the above described
 well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas)
) ss:
 County of Sedgwick)

Subscribed and Sworn to before me a Notary Public
 in and for said county and state this 1st day of July, 1980.

7-3-80
 RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

Elsie Willison
 Elsie Willison - Notary Public

My Commission Expires:
 July 25, 1982