

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-10036-0000
API NUMBER Unknown

LEASE NAME Cudney

WELL NUMBER B-1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 25 SRGE. 16 (W)

COUNTY Edwards

Date Well Completed unknown

Plugging Commenced 12-6-85

Plugging Completed 12-18-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR LASMO Energy Corporation

ADDRESS Box 1365, Great Bend, Kansas 67530

PHONE# 316, 792-2585 OPERATORS LICENSE NO. 4678

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist #1

Is ACO-1 filled? yes if not, is well log attached?

Producing Formation unknown Depth to Top 4400 Bottom 4376 T.D. 4490

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	373	0
				5 1/2	4489	2194

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Bottom plug - pumped 100# hulls 30 sks cement to 4200'

Top plug 3 hulls, 15 gel 60 sks 60-40 pox 6% gel 10 gel 1 hull
8 5/8 plug 110 sks cement
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Wesley Siroky (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wesley Siroky

(Address) Box 768, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 19 day of December, 19 85

Carmen R. Cook
Notary Public
STATE CORPORATION COMMISSION



12-20-85 DEC 20 1985

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

Cud B#1

[Handwritten signature]

DRILLER'S LOG

COMPANY: Inger Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: CUDNEY "B" #1
 LOCATION: C SW SE Sec. 27-25S-16W
 EDWARDS COUNTY, KANSAS
 COMMENCED: 7-25-62
 COMPLETED: 8-8-62

[Handwritten marks]

0	40	Sand
40	130	Sand & Shale
130	373	Shale
373	710	Shale & Shells
710	1071	Shale, Shells & Redbed
1071	1101	Anhydrite
1101	1740	Shale & Shells
1740	2115	Shale & Lime
2115	2655	Lime
2655	2770	Lime & Shale
2770	2815	Shale
2815	3000	Lime & Shale
3000	3220	Shale & Lime Streaks
3220	4424	Lime
4424	4460	Lime & Shale
4460	4490	Shale & Lime
	<u>4490</u>	<u>Rotary Total Depth - Set 5 1/2" Casing</u>

Set 8 5/8" Used surface casing @ 373' Cemented with 275 sacks of Common HA5.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Cudney B-#1 located C SW SE of Section 27, Township 25 South, Range 16 West of Edwards County, Kansas, as reflected by the files of Leben Drilling, Inc.

[Signature: Byron Johnson]
Byron Johnson

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 9th day of August, 1962.

[Signature: Ulanda Nichols]
Ulanda Nichols

My Commission Expires:
April 1, 1963

11-7-85
RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1985
CONSERVATION DIVISION
Wichita, Kansas