

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Edwards County. Sec. 27 Twp. 25 Rge. ~~XX~~16 (W)

Location as "NE/CNWxSWx" or footage from lines. C NE SW

Lease Owner NATIONAL COOPERATIVE REFINERY ASSOCIATION

Lease Name Floyd Cudney Well No. 1

Office Address P. O. Box 6, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed July 14, 1961

Application for plugging filed October 11, 1971

Application for plugging approved October 13, 1971


Plugging commenced December 16, 1971

Plugging completed December 16, 1971

Reason for abandonment of well or producing formation This well was
no longer economic to produce.

If a producing well is abandoned, date of last production August 21, 1970

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well G. R. Beberstein

Producing formation Conglomerate Depth to top 4370' Bottom 4404' Total Depth of Well 4416 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	None
				5 1/2"	4429'	3099.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2070' KB. T.D. 4428'. PB TD 4416'. Production in Conglomerate formation thru perf. @ 4392-4395' & 4372-4376'. Moved in. Rigged up. Sand back from 4416' to 4350'. Dump 5 sxs. cem. stop @ 3293 and 3090'. Pull 3099.35' - 5 1/2" csg. Globe Cementing Co. pumped 2 sxs. hulls, 15 sxs. Gel and 100 sxs. cem. to surface. Complete 12:30 PM, December 16, 1971. Earl Baker - Company Representative.

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Comstock Pipe Pulling Company

Address 320 North Park, Stafford, Kansas 67578


STATE OF KANSAS, COUNTY OF BARTON, ss.

I. J. Gotsche (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) *I. J. Gotsche*
I. J. Gotsche, District Superintendent
P. O. Box 6, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 1971.



Russell E. Turnbow
Russell E. Turnbow Notary Public.

April 14, 1975