

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-067-10029-0000
API NUMBER N/A Drld.9/23/6

LEASE NAME Appleman

WELL NUMBER 1 SWDW

SPOT LOCATION SE SE

SEC. 36 TWP. 27 RGE. 35 (X) or (W)

COUNTY Grant

Date Well Completed 9/30/65

Plugging Commenced 4/3/85

Plugging Completed 5/15/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KOCH EXPLORATION COMPANY

ADDRESS P.O. Box 2256, Wichita, KS 67201

PHONE # (316) 832-5483 OPERATORS LICENSE NO. 6477

Character of Well TA SW Inj. well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 Dodge City, KS

Is ACO-1 filed? No/Drld. If not, is well log attached? No, mailed w/Form CP-1 4/10/85

Injection 6/23/65
~~Production~~ formation Glorietta Sd. Depth to top 1418 bottom 1620 T.D. 1626

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
N/A				5-1/2"	1628'	120' (junk)

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 2-3/8" tbq., 5-1/2" csg. scraper & 4-3/4" bit in hole. Top of fish 637', bottom of fish 1315'. Unable to fish due to obstruction above top of fish. Run W.P. & wash over 2-3/8" tbq. to 852'. Circ. & spot 50 sx cmt. plug 60/40 Poz mix 6% Gel, 2% CaCl from 852' up to surface - 4/30/85 @ 4:30 P.M. Plugging witnessed by state rep. Mr. Robert Tarbutton

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor None required used Dowell to spot cmt. License No. 6-19-1985
Address _____

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.


JUN 19 1985

Vernon J. Lowe (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Vernon J. Lowe

(Address) P.O. Box 2256, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 85



Georgia A. George
Notary Public

My Commission expires: _____