

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-21,306-0000

LEASE NAME Gregory

WELL NUMBER 1-31

410' Ft. from S Section Line

4775' Ft. from E Section Line

SEC. 31 TWP. 25 SRGE. 16W (XXXX)(W)

COUNTY Edwards

Date Well Completed 12-7-87

7:00 AM

Plugging Commenced 12-7-87

8:30 AM

Plugging Completed 12-7-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167
 Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	308' KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Fill hole with heavy mud. Plugged with 50 sacks at 1170'; 40 sacks at 610';
40 sacks at 330'; 10 sacks 0 to 40'. 15 sacks in rathole. Used 60/40 Pozmix
with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
 Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner

(Address) F. A. Wuellner, Secretary
 P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 87



Agnes D. Wurst
 Notary Public

My Commission Expires: 4-6-89

STATE CORPORATION COMMISSION
 DEC 10 1987
 12-10-87
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 07-86

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - GREGORY #1-31

Located: S/2 SW SW, Section 31-25S-16W, Edwards County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 30, 1987

COMPLETED: December 7, 1987

TOTAL DEPTH: 4630'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 110 Surface Soil and Sand	Ran 7 joints 8 5/8" casing. 295.10'
110 - 200 Shale - Clay	pipe set at 308' K.B. Cemented with
200 - 312 Shale	225 sacks 60/40 Pozmix, 3% cc. Plug
312 - 1020 Shale, Sand, Red Bed	down at 6:15 PM, 11-30-87, by Howco.
1020 - 1118 Shale and Lime Stringers	
1118 - 1134 Anhydrite	
1134 - 1850 Shale and Lime Stringers	
1850 - 4630 Lime and Shale	Plugged.

Deviation Surveys: 2° at 2100'
2° at 4630'

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1987

CONSERVATION DIVISION
Wichita, Kansas