


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-647-00406-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Edwards County, Sec. 31 Twp. 25S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Pickrell Drilling Company
Lease Name Wilson "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 19, 19 60
Application for plugging filed December 19, 19 60
Application for plugging approved December 19, 19 60
Plugging commenced December 19, 19 60
Plugging completed December 19, 19 60
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 S. Main, St. John, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4641' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	319'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 300'. Set plug. Cement with 30 sks.
Heavy mud to 45'. Set plug. Cement with 15 sks to
bottom of cellar. Plug rat hole with 2 sks cement.
The above operation was performed by Globe Oilwell
Cementing equipment.

12-28-60

DEC 28 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 60

My commission expires March 7, 1964 Marilyn A. Davis Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Building
 Wichita, Kansas
 LOCATION: WILSON "B" #1, SW SW NE
 Sec. 31-25S-16W, Edwards County, Kansas
 CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas
 CASING RECORD: Ran 8 jts. 8 5/8" 22.7# Spiralweld casing. Set at 319' w/250 sks. Circ. D & A, no oil string.
 Rotary Drilling, Commenced 12-5-60
 Rotary Drilling Completed 12-19-60

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

170	Sand		<u>Circulate for Samples</u>
185	Clay, sand		
320	Blue shale	4060	
490	Sand, shale	4100	
1115	Red Bed	4145	
1145	Anhydrite	4397	
2180	Shale, shells	4452	
2220	Shale, shells, lime	4457	
2300	Lime, shale	4462	
2781	Lime	4467	
3075	Lime, shale	4472	
3255	Shale, lime	4482	
3715	Lime, shale	4492	
3766	Lime	4502	
4016	Lime, shale	4512	
4180	Lime	4641	
4250	Lime, shale strks		
4371	Lime		<u>Sloper Test</u>
4410	Lime, shale	320' 0°	
4455	Lime, shale, chert	1000' 0°	
4512	Miss.	1500' 0°	
4561	Chert	3500' 0°	
4641	Viola - T.D.	4575' 0°	

12-28-60

CONSERVATION DIVISION
Wichita, Kansas

S.D.M.
 1000' OK
 2000' OK
 3000' OK
 4641' OK

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 29th day of December, 19 60, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

Marilyn A. Davis
 Notary Public
 Marilyn A. Davis