

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,484 ⁰⁰⁰⁰
LEASE NAME Orlyn Parker #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____
SPOT LOCATION C SW NE
SEC. 30 TWP. 25 RGE. 16 (E) or (W)
COUNTY Edwards
Date Well Completed _____
Plugging Commenced 10/25/84
Plugging Completed 11/1/84

LEASE OPERATOR John Jay Darrah, Jr.
ADDRESS 405 Centruy Plaza, Wichita, Ks. 67202

PHONE # (316) 263-2243 OPERATORS LICENSE NO. 5088

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4472'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	340'	none
				4 1/2"	4471'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 30 sacks cement to 3995'. Shot pipe at 3700', 3500', 3200', 3000', 2800', 2600', 2400'. Pulled 65 joints of pipe. Plugged well with 175 sacks 60/40 poz. 2% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
11-8-84
NOV 08 1984
CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1984



My Commission expires:

Irene Hoover
Notary Public

Pintail Petroleum
1010 Century Plaza Bldg.
Wichita, Kansas 67202

- Orlyn Parker #1
C SW NE Sec. 30-25S-16W
Edwards County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: February 24, 1979
Completed: March 3, 1979

Drillers Log

Sand	125
Blue Shale	343
Red Bed	1102
Anhydrite	1115
Shale	2046
Shale & Shells	3870
Shale & Lime	4225
Lime & Shale	4365
Lime	4472 RID

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1984

CONSERVATION DIVISION
Wichita, Kansas