

API NUMBER 15-047-20842-0000

LEASE NAME Yung

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 30 TWP. 25 SRGE. 16 W. (S) or (N)

COUNTY Edwards

Date Well Completed

Plugging Commenced 1/18/89

Plugging Completed 1/23/89

RECEIVED
FEB 2 1989
2-2-89
CONSERVATION DIVISION
Wichita, Kansas
LEASE OPERATOR D.R. Lauck Oil Co., Inc.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

ADDRESS Box 488 Ellinwood, KS 67526

PHONE# (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4511'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	365	none
				4 1/2	4493	2724

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4390', dumped 3 sacks cement. shot @ 3228', 2724', plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls, 8 5/8 plug 125 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D.R. Lauck Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1989

James Hoover
Notary Public

My Commission Expires:



15-047-20842-0000

D. R. Lauck Oil Company, Inc. - Yung #1
221 S. Broadway, Suite 400 SE NW SW Sec. 30-25S-16W
Wichita, Kansas 67202 Edwards County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: March 26, 1981
Completed: April 2, 1981

Drillers Log

Sand	160
Blue Shale	550
Red Bed	1112
Anhydrite	1125
Red Bed & Shale	1620
Shale & Shells	3295
Shale & Lime	4240
Lime & Shale	4335
Shale & Lime	4420
Lime	4498 RTD

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1988

CONSERVATION DIVISION
Wichita, Kansas