

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Hamilton County, Sec. 27 Twp. 24S Rge. 41 (W)

Location as "NE/CNW/SW" or footage from lines 100' N & W of Ctr.

Lease Owner Texaco Inc.

Lease Name H. W. Gregory Well No. 1

Office Address 614 Bitting Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Gas (SI)

Date well completed 11-28-19 63

Application for plugging filed 10-21-19 66

Application for plugging approved 10-25-19 66

Plugging commenced 11-2-19 66


Plugging completed 11-2-19 66

Reason for abandonment of well or producing formation Well could not be swabbed down enough to produce gas.

If a producing well is abandoned, date of last production (Test) 11-28-19 63

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well E. Eves, Sublette, Kansas

Producing formation Winfield Depth to top 2351 Bottom 2360 Total Depth of Well 2390 Feet

Show depth and thickness of all water, oil and gas formations. PBTD 2365

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Winfield	Gas	2351	2360	7"	260'	None
				4 1/2"	2390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged as follows: 2365-2100 w/10 sxs cmt, 2100-300 w/drlg mud, 300-100 w/10 sxs cmt, 100-60 w/drlg mud, 60-0 w/5 sxs cmt. Comp 4 PM 11-2-66. No casing recovered.

12-15-66

STATE CORPORATION COMMISSION

DEC 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service, 121 West 9th  
Address Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. M. R. Wilson

(employee of owner) or (~~owner representative~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson

614 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December 19 66

Peggy Sue Jones  
Notary Public.

My commission expires 10-13-69



15-075-10115-0000

LEASE: H. W. GREGORY NO. 1  
OWNER: TEXACO INC.  
CONTRACTOR: EARL F. WAKEFIELD  
COMM: 11-14-63  
COMP: 11-17-63

LOCATION: NW/4  
Section 27-24S-41W  
Hamilton County, Kansas  
CASING: 7" Set at 160'  
4 1/2" Set at 2390'

Surface Soil	20
Sand and Clay	60
Blue Shale, Shale and Shells	260
Shale and Red Bed	300
Sand	330
Shale	584
Sand	628
Shale	777
Anhydrite	808
Shale, Red Beds, Shells	1309
Salt and Red Bed	1535
Red Beds and Shale	1665
Red Bed	1834
Anhydrite	1849
Red Bed and Shells	1935
Red Bed and Shale	2307
Lime and Shale	2390
R.T.D.	

10-25-66  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 25 1966  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log on the H. W. GREGORY NO. 1 well, located in the NW/4 of Section 27-24S-41W, Hamilton County, Kansas.

EARL F. WAKEFIELD

BY Earl F. Wakefield

Subscribed and sworn before me this 26 day of November, 1963.

My commission expires:  
January 25, 1965

Wanda W. Riley  
WANDA W. RILEY NOTARY PUBLIC