

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1972 11-22-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Acme Oil Corporation

Complete Address 6235 W. Kellogg, Wichita, Kansas

Lease Name Callias Well No. 1

Location SE SE NE Sec. 26 Twp. 25 Rge. 4 (E) (W) X

County Reno Total Depth 4081'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 5 AM Day 17 Month November Year 1972

The above well was plugged as follows:

Hole filled with mud to 240'. Plug and 1/2 sack hulls pushed to 240' and hole cemented  
with 25 sacks cement through drill pipe. Hole filled with mud to 40'. Plug and 1/2  
sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.  
Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*  
Well Plugging Supervisor

INVOICED  
DATE 11/22/72  
INV. NO. 6658-W