

15-075-00076-0000

Form CP-3
Rev. 6-26-62

40-
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-17-64
JUL 17 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name Foreman-Trust Unit Well No. # 7

Location C NW SE Sec. 23 Twp. 24 Rge. (E) (W) 39

County Hamilton Total Depth 2550'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 578

Operation Completed: Hour 7 PM Day 15 Month 7 Year 64

The Above well was plugged as follows:

8 5/8"-367' Circulated w/cement. 4 1/2"-2549' Cemented. Top Perforations 2352'

Plug bottom w/10 Sax. cement-top cement 2283' Mud 2283' to 600'

Spotted 25 Sax. cement 600' to 525' Mud 525' to 350'

Spotted 25 Sax. cement 350' to 275' Mud 275' to 45'

Plug 15 Sax. cement 45' to 0 Pulled 2024' 4 1/2" pipe.

Company Pump. Cut surface off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/17/64
INV. NO. 9494-W