

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 8 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Home Stake Production Company

Complete Address 10th Floor Philktower Bldg., Tulsa, Oklahoma 74103

Lease Name G. T. Inge Well No. 1

Location SE NE SW Sec. 29 Twp. 24 Rge. 41 (E) (W)

County Hamilton Total Depth 2410'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 e. 6th, Ellinwood, Kansas License No. 396

Operation Completed: Hour 4:00PM Day 2 Month 9 Year 1972

The above well was plugged as follows:

8 5/8" to 416' circulated w/ cement. 5 1/2" to 2410' cemented.

Top perforations 2346' Plug bottom w/ 20 sacks cement.

Top of cement 1900' Mud 1900' to 400'

Spotted 35 sacks cement 400' to 300' Mud 300' to 45'

Plug. Halls 15 sacks cement 45' to 0'. Halliburton Pump Truck.

Pulled 1407' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9/12/72

INV. NO. 6295-W