

*J.P.*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

NOV 4 1966  
CONSERVATION DIVISION

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Building , Wichita, Kansas

Lease Name H.W. Gregory Well No. 1

Location App. Center Sec. 27 Twp. 24 Rge. 41 (E) (W)

County Hamilton Total Depth 2390'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 6:30PM Day 2 Month 11 Year 1966

The Above well was plugged as follows:

7" to 260' circulated w/ cement. 4 1/2" to 2390' circulated w/ cement.

Plug bottom w/ 10 sacks cement. Top of cement 2100'

Mud 2100' to 300' Spotted 10 sacks cement 300' to 200'

Mud 200' to 60' Plug, Hulls & 5 sacks cement 60' to 0'.

No Casing Pulled. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edwards J. Eves*  
Well Plugging Supervisor

DATE 11/4/66

INV. NO. 4232-u