

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,194 - 0000

LEASE NAME Cross

WELL NUMBER 2-18

         Ft. from S Section Line

         Ft. from E Section Line  
NW NW SE

SEC. 18 TWP. 24 RGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 7-23-87

Plugging Completed 7-27-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl Estate

ADDRESS P.O. Box 780167  
Wichita, Kansas 67278-0167

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	265'	none
				4-1/2"	4445'	2561'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom was already squeezed. Shot pipe @2806', 2561', pulled a total of 63 joints of 4-1/2" casing. Plugged surface with 250# hulls, 10 gel, 50 cement, 10 gel, 50# hulls, plug and 125 cement, 60/40 pos, 6% gel.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 17th day of September 1987

Irene Hoover  
Notary Public

My Commission Expires:         



RECEIVED  
CONSERVATION DIVISION,  
Wichita, Kansas  
9-21-87  
Form CP-4  
Revised 07-86

15-047-21194-0000

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- CROSS #2-18

Located: NW NW SE, Section 18-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 12, 1984

COMPLETED: July 18, 1984

TOTAL DEPTH: 4550'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing. 252.56' pipe set at 265' K.B. Cemented with 210 sacks 60/40 Pozmix, 3% cc. Plug down at 1:00 PM, 7-12-84, by Howco.
90 - 268 Clay and Shale	
268 - 1179 Shale and Sand	
1179 - 1190 Anhydrite	
1190 - 1380 Shale	
1380 - 2189 Shale and Lime Stringers	
2189 - 4440 Lime and Shale	
4440 - 4530 Chert and Shale	
4530 - 4550 Lime and Shale	Ran 112 joints 4 1/2", 10.5# casing. 11 joints were used. 4535.89' pipe set at 4545' K.B. 5' off bottom. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix, plus our regular additives. Plugged rathole, pulled water well and plugged. Plug down at 3:15 PM, 7-18-84, by Howco. (There is a Halliburton wire line weight in hole.)

Deviation Surveys: 1° at 2189'  
3/4° at 4440'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1987

ENGINEERING DIVISION  
JUN 18 1987