

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-047-21,296 - 0000

LEASE NAME Cross "A"

WELL NUMBER 1=18

2970' Ft. from S Section Line

3630' Ft. from E Section Line

SEC. 18 TWP. 24 SRGE. 17 ~~W~~ W

COUNTY Edwards

Date Well Completed 10-29-87

9:00 PM

Plugging Commenced 10-29-87

10:30 PM,

Plugging Completed 10-29-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167  
 Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing Formation                      Depth to Top                      Bottom                      T.D.                     

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	294.76'	None
					306' KB	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. 50 sacks at 1230'; 40 sacks at 650'; 40 sacks at 440';  
 10 sacks 40' to 0'. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129  
 Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Harry J. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

STERLING DRILLING COMPANY  
 (Signature) Harry J. Mead  
 (Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 2nd day of STATE November, 19 87

Agnes D. Wurst NOV 4 1987 11-4-87  
 Agnes D. Wurst - Notary Public

My Commission Expires:                     



CONSERVATION DIVISION  
 Wichita, Kansas

Form CP-4  
 Revised 07-86

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CROSS "A" 1-18

Located: SW SE NW, Section 18-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 22, 1987

COMPLETED: October 29, 1987

TOTAL DEPTH: 4655'

LOG

CASING RECORD

0 - 80 Surface Soil and Sand  
 80 - 130 Red Shale  
 130 - 585 Shale  
 585 - 1181 Shale and Lime  
 1181 - 1197 Anhydrite  
 1197 - 3840 Shale and Lime  
 3840 - 3995 K. C. Lime  
 3995 - 4655 Lime and Shale

Ran 7 joints 8 5/8" casing. 294.76'  
 pipe set at 306' K.B. Cemented with  
 225 sacks 60/40 Pozmix, 2% gel and  
 3% cc. Plug down at 7:30 PM, 10-22-87,  
 by F. B. Titan.  
  
 Plugged.

Deviation Surveys: 3/4° at 3006'  
1° at 4498'

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-4-87  
 NOV 4 1987

CONSERVATION DIVISION  
Wichita, Kansas